



CITY OF COLUMBIA, MISSOURI

FINANCE DEPARTMENT
PURCHASING DIVISION

NOTICE TO BIDDERS ADDENDUM #2 RFQ #51/2018

CLARY SHY AGRICULTURE PARK

Bidders shall note these changes to the above Request for Quotation and *incorporate these changes in their submittal*. Bidders shall attach a signed acknowledged copy of this addendum to their bid, if submitting a hard copy (via paper) or agree to the addendum electronically if submitting through the electronic bid system on line.

The following revisions and/or additions shall be referred to as part of the Bid/Contract Documents.

General Clarifications:

1. Line Item Sheet attached
2. No other changes

ACKNOWLEDGEMENT OF ADDENDUM #2

The undersigned Respondent hereby certifies that the changes set forth in this Addendum #2 have been incorporated in their proposal and are a part of Request for Quotation No. 51/2018 other provisions of the bid documents, except as herein stated, shall remain in force as written.

Firm _____ Date _____

Signed _____

Line Items - Clary-Shy Agriculture Park

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
1	Mobilization	LS	1		
2	Removal of sidewalk	SY	234		
3	Removal of asphalt	SY	5611		
4	Removal of Curb & Gutter	SY	686		
5	Removal of Fence	LF	366		
6	8" Concrete Pavement	SY	3713		
7	6" Concrete Pavement	SY	2171		
8	5" Concrete Sidewalk	SY	1519		
9	6" Aggregate Base	SY	5884		
10	4" Aggregate Base	SY	1519		
11	3' Aggregate Base (Veggie Wash at Barn)	SY	7		
12	Asphalt Pavement Patch	SY	482		
13	Curb and Gutter	LF	793		
14	4" Yellow Pavement Marking	LF	2300		
15	Pavement Marking- 24" White Crosswalk Bar Type 2 Preformed Pavement Marking Tape	LF	206		
16	Detention Basin	CF/storage	173000		
17	Detention Outlet Structure	EA	1		
18	Bioswale	SF	7700		
19	Nyloplast Curb Inlet	EA	4		
20	HDPE Storm Pipe	LF	300		
21	Area Inlet/Junction Box	EA	7		
22	Roof Drain	LF	2000		
23	Erosion Control	LS	1		
24	Seeding and Mulching	LS	1		
25	Earthwork	LS	1		
26	Construction Staking	LS	1		
27	Concrete Footings (10'x10'x2')	EA	36		
28	Concrete Grade Beams	EA	20		
29	Concrete Floor Slab (5")	SF	30455		
30	Pre-Engineered Metal Building	SF	13550		
31	Masonry (CMU)	SF	2340		
32	Metal Framing (overbuild at Restrooms)	Ea	1		
33	Insulation (rigid board)	SF	2340		
34	Insulation (Overbuild above Toilet)	SF	1020		
35	Soffit Panels	SF	18000		
36	Metal Wall Panels	SF	3020		
37	Gutters	LF	480		
38	Downspouts	EA	18		
39	Doors/Frames/Hardware	Ea	5		
40	Doors (Overhead coiling)	EA	3		
41	Painting (columns)	EA	20		
42	Painting (CMU)	SF	1450		
43	Painting (Ceilings)	SF	1020		
44	Toilet Accessories	EA	1		
45	Toilet Partitions	EA	4		
46	Water Coolers	EA	3		
47	Bike Racks	EA	12		
48	Bike Corrals	EA	6		
49	Fire Suppression System	SF	13550		

50	Fire Extinguishers	EA	6		
51	Parking Signs (Accessible)	EA	2		
52	Bollards (Concrete-filled steel tube)	EA	36		
TOTAL BASE BID					

ALTERNATE #1 VINYL CURTAINS

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
53	Vinyl Weather Curtains (11' x 10')	LS	1.0		

ALTERNATE #2 BARN

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
54	8" Concrete Pavement	SY	531.0		
55	6" Concrete Pavement	SY	242.0		
56	5" Concrete Sidewalk	SY	41.0		
57	6" Aggregate Base	SY	840.0		
58	4" Aggregate Base	SY	41.0		
59	Concrete Footings (3'dia x 8')	EA	22		
60	Concrete Footings (2'dia x 4')	EA	14		
61	Concrete Footings (strip)	LF	426		
62	Concrete Floor Slab (5")	SF	6,420		
63	Insulation (roof)	SF	3,864		
64	Wood Framing (Barn Structure)	SF	3,840		
65	Wood Framing (Barn Mezzanine)	SF	1,000		
66	Wood Framing (Barn Germination Room)	EA	1		
67	Metal Wall Panels	SF	4,500		
68	Metal Roof Panels	Roof Sq	45		
69	Doors/Frames/Hardware	Ea	4		
70	Stairs/Railing/Mezzanine Railing	LS	1		
71	Bollards (Concrete-filled steel tube)	EA	12		
TOTAL ALTERNATE #2 COST					

ALTERNATE #6 NORTH TIER PARKING

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
72	Removal of Curb & Gutter	SY	40		
73	6" Concrete Pavement	SY	1,453		
74	6" Aggregate Base	SY	1,453		
75	Curb and Gutter	LF	560		
76	4" Yellow Pavement Marking	LF	700		
77	Parking Signs (Accessible)	EA	2		
TOTAL ALTERNATE #6 COST					
TOTAL BASE - ALT 1 - ALT 2 - ALT 6					