

ADDENDUM #3

DATE: **May 9, 2018**

PROJECT MANUAL FOR: **SCHRENK HALL PHASE IIA RENOVATION**

PROJECT NUMBER: **264005**

ADVERTISEMENT DATE: **APRIL 9, 2018**

PREPARED FOR: **The Curators of the University of Missouri**

CONSULTANT: **THE CLARK ENERSEN PARTNERS
1251 NW Briarcliff Parkway, Suite 400
Kansas City, MO 54116
(816) 474-8237**

Drawings and Specifications for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

SPECIFICATIONS:

Item 3-1: Section 1.F.1 Allowances

Add the following new subsection 1.F.1 Allowances after Section 1.F Alternates.

1.F.1 Allowances

Provide an allowance of \$9,000 to be paid to the controls contractor for Time and Material work on a not to exceed basis. The work shall include the relocation of BAS control wiring and panels currently install on and/or near the existing AHU-1. The work shall occur prior to the demolition of AHU-1 and will be directed by MS&T construction manager, Ron Boggs. The controls components shall be re-installed on a self-supported Unistrut assembly that is independent of the AHU casing.

Item 3-2: 07 42 13 – Metal Plate Wall Panels

Refer to 2.2.A.2. Subject to compliance with all specified requirements, Centria EcoScreen Perforated Panels is an approved alternate product for Metal Plate Wall Panels.

Refer to 2.2.A.2. Subject to compliance with all specified requirements, Pac-Clad Corrugated Wall Perforated Panels is an approved alternate product for Metal Plate Wall Panels.

Item 3-3: 09 51 13 – Acoustical Panel Ceiling

Refer to 2.1.A.2. Subject to compliance with all specified requirements, Certainteed is an approved manufacturer for Acoustical Panel Ceiling.

Item 3-4: 10 44 13 – Fire Protection Cabinets

Refer to 2.2.D. Recessed Cabinet: This cabinet is FEC-2 in the documents

Refer to 2.2.E. Semi-recessed Cabinet: This cabinet is FEC-1 in the documents.

DRAWINGS:

Item 3-5: G0.11 – Ground Floor Code Compliance Plan – Base Bid

Replace existing G0.11 in its entirety with new attached G0.11. Note tagged FEC-1 & FEC-2 locations.

Item 3-6: A0.10 – Ground Floor Base Bid Demolition Plan, Demolition Notes, Demolition Key Notes

Replace existing A0.10 in its entirety with new attached A0.10. Note updated tags and Demolition Key Notes.

Item 3-7: A0.11 – First Floor Base Bid Demolition Plan, Demolition Notes, Demolition Key Notes

Replace existing A0.11 in its entirety with new attached A0.11. Note updated tags and Demolition Key Notes.

Item 3-8: A0.12 – Ground Floor & First Floor Alternate Demolition Floor Plans

Replace existing A0.12 in its entirety with new attached A0.12. Note updated tags and Demolition Key Notes.

Item 3-9: A1.10 – Ground Floor Base Bid Plan, Floor Slab Infill Details

Replace existing A1.10 in its entirety with new attached A1.10. Note updated tags.

Item 3-10: A1.11 – First Floor Base Bid Plan

Replace existing A1.11 in its entirety with new attached A1.11. Note updated tag location.

Item 3-11: A1.12 – Ground Floor & First Floor Alternate Floor Plans

Replace existing A1.12 in its entirety with new attached A1.12. Note updated tags.

Item 3-12: A7.10 – Plan Details

Replace existing A7.10 in its entirety with new attached 7.10. Note updated details #1 and #3.

END OF ADDENDUM #3