

ADDENDUM NO. 2

TO: PLANS AND SPECIFICATIONS FOR STATE OF MISSOURI

**Chilled Water Plant Optimization
Harry S Truman State Office Building
Jefferson City, Missouri
PROJECT NO.: O1808-01**

Bid Opening Date: 1:30 PM, Thursday, September 20, 2018 (Not Changed)

Bidders are hereby informed that the construction Plans and/or Specifications are modified as follows:

SPECIFICATION CHANGES:

1. Section 011100 – Summary of Work
 - a. ADD Paragraph 1.8-B as follows:
 - B. All loud demolition work, particularly removal of the house keeping pads, shall be done outside of business hours. Owner shall be notified a minimum of 72 hours in advance of this demolition.

DRAWING CHANGES:

1. Sheet M-101
 - a. CLARIFICATION: The intent of Demolition Note #1 is to reuse as much of the existing piping and infrastructure as possible for new work. This includes the existing basket strainer and housekeeping pad. Note that the existing housekeeping pads reused for pumps TRWCP-3 & 4 may have to be modified to fit the new pump selected by the contractor.

ATTACHMENTS:

None

September 13, 2018

END ADDENDUM NO. 2